

The Duplex Pipe Organ and Blower Company Ltd.

42, Weybourne Road,

Farnham,

Surrey.

GU9 9HG

Telephone/Fax: 01252 672290

e-mail:jamescz121@aol.com

Wednesday, 04 November 2020

Proposed Next Stages and Costings for the Ongoing Rebuilding of the Organ at St. Peter's Church, Streatham

Works to Be Undertaken

Urgent Additional Works to the Front Casework

These works will not put the organ out of action but will compromise a number of stops with basses in the front of the case. The proposed works include the cleaning, repair and refinishing of the front pipes in Ardenbright Silver. This will necessitate the use of the Choir Vestry if carried out in the colder less predictable winter months. As part of the works we will be bringing our own tower scaffolding to site to assist in the removal and refitting. This is a lightweight unit with a modest foot print that is easily assembled and dismantled so will not need to be left erected in the church when not in use.

- Removal of the front case pipes and casework down to the level of the window console.
- Cleaning and repair of the front pipes and any conveyancing removed from the front tip block.
- Manufacture of new structural timberwork for the secure support of the front casework from the existing building frame.
- Repair and cleaning of original casework panels, rails and posts.
- Cleaning of the front pipes and refinishing with stabilizing undercoat and Ardenbright Silver with a lacquer top coat for durability.
- Refitting of the casework and front pipes.

Total.....£7970.00

Plus VAT @ 20%

The only caveat, concerning these works, are current problems with the front pipes, either due to conveyances or actions that are inaccessible with the casework and Great in place. We would hope to make any necessary repairs in this area at the same time.

Choir Diapason Bass Chest, Pipework and Tubing

Cleaning, repair and overhaul of Diapason Bass chest and pipes. The chest currently has pneumatic action tubed from the Choir soundboard action. On the whole I would recommend conversion to electric action so that the tubing run can be removed and the action made more reliable for the future. Whilst the current electromechanical switching is in place some provision would have to be made for connection to allow the chest to operate with the Diapason stop action.

Total.....£3125.00
Plus VAT @ 20%

Electrification of the Treble End Jamb and Rebuild of the Great Slider Action

This will completed the drawstop electrification of the organ and slider unit conversion and overhaul. It also includes the provision of all new drawstop bushes in polished ebonite for both bass and treble end jambs.

Total.....£8384.00
Plus VAT @ 20%

This covers all the immediate proposed works.

With all best wishes

James Richardson-Jones(Director)